

KANSAS

*16*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 26 1966  
4-26-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Eason Oil Company

Complete Address: 5225 N. Shartel, Oklahoma City, Oklahoma

Lease Name Schuette Well No. # 2-1

Location C W/2 Sec. 1 Twp. 32 Rge. 16 (E)    (W) W

County Comanche Total Depth 4879'

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Red Tiger Drilling Company

Address: 1720 Wichita Plaza, Wichita, Kansas License No.   

Operation Completed: Hour 11:00 PM Day 24th Month April Year 1966

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cement circulated. Hole was filled with  
drilling mud to 250', 1st cementing plug, bridged with 1/2 sacks of hulls  
on fluid at 250', and cemented with 25 sacks. Hole was filled with  
drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls  
on fluid at 40', and cemented with 10 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/26/66  
INV. NO. 3119-u