

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials and signature

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE-NE-SW

SEC. 36 TWP 31 RGE. 20W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease LORIMOR "A"

Operator M. B. Garner Address 710 1st St
Wichita Kansas

Field _____ County Comanche

Total Depth 5286 Feet.

Plugging Contractor Co Joals. Speck Moore J.P.

Plugging Contractor's License No. DR

Address Wichita Kans.

(Describe briefly the manner in which the well was plugged)

*13 7/8" 317' C.W.C. 10" 998' cemented with 150-4
Mud to 600' set Plug run 20' cement
pull some 10" Mud to 300' set Plug run 35' cement
cement in 13 7/8" through Drill pipe Mud to
20' set plug filled to base of tube with cement
reason for 600' Plug in 10" and 300' Plug in 13 7/8"
had cement blowout at 360' while being drilled
leaves cement Plug both above
and below Blowout point*

M. L. Rice
District Conservation Agent

Date 9-14-53

RECEIVED

9-16-55

PLUGGING
FILE NO. SEC 36 T 31 R 20W
BOOK PAGE 150 LINE 28