

 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued January 19, 1968.

RECEIVED  
STATE CORPORATION COMMISSION  
1-26-68  
JAN 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita Kansas 67202

Lease Name Robbins Well No. # 1

Location C NW NW Sec. 7 Twp. 31 Rge. 18 (E) (W) W

County Comanche Total Depth 5300'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Kerr Well Service

Address: Box 1045, Pratt Kansas 67124 License No. 615

Operation Completed: Hour 5:15PM Day 24th Month January Year 1968

The Above well was plugged as follows:

412' of 8 5/8" surface pipe, cement circulated. 5233' of 4 1/2" long string,  
cemented with the top of the cement at 4684'. Top perferation 4945'. Bottom  
of the hole was sanded to 4900', and cemented with 4 sacks, with cement  
from 4900' to 4850'. 4690' of 4 1/2" long string was recovered from the hole.  
Fluid in the hole was at 360', bridge plug and rock bridge from 360' to  
350', and cemented with 25 sacks, with cement from 350' to 275'. Hole was  
filled with mud to 40', rock bridge from 40' to 30', and cemented with  
10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/26/68  
INV. NO. 7154-W

Signed: Audie Elving  
Well Plugging Supervisor