



CP3

GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

**State Corporation Commission**  
**CONSERVATION DIVISION**  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 16 1959  
 11-16-59  
 CONSERVATION DIVISION  
 Wichita, Kansas

Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date 27 Oct -, 1959, authorized the following plugging operation:

Operator's Full Name: Coyette Drilling Co.

Complete Address: 814 Union Court Bldg, Wichita, Kas

Lease Name: Burdick Well No. 1

Location: CNE NE Sec. 6 Twp. 31 Rge. 18 (E) (W)

County: Comanche Total Depth: 5157

Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

490' of 8" surface casing. Fill hole to 490'  
with heavy drilling mud. Set Cementing plug  
at 475' and pour 20 sack cement through drill  
pipe. Fill hole to 55' with heavy mud. Set  
Cementing plug at 55'. Pour 10 sack cement  
to base of casing.

Very truly yours,

Signed: [Signature]  
 Conservation Division Agent