

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed March 27, 1967.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 6 1967
4-6-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: P. O. Box 308, Great Bend, Kansas

Lease Name Clarke "B" Well No. # 1

Location APP C NE SW
1905' FSL & 1980' FWL Sec. 12 Twp. 31 Rge. 18 (E) (W) W

County Comanche Total Depth 677'

Abandoned Oil Well Gas Well Input Well SWD Well D & A ✓

Other well as hereafter indicated: This hole was lost drilling surface hole, and rig will be skidded 75' south.

Plugging Contractor: Peel Brothers, Inc.

Address: Box 359, Hoisington, Kansas License No.

Operation Completed: Hour 1:30PM Day 3rd Month April Year 1967

The Above well was plugged as follows:

When drilling 12½" surface hole to 677', circulation was lost causing a washed out cavity below the ground level, the cellar caved in, and the ground around the rig cratered, filling the 12½" surface hole that had been drilled. The top of the red bed had been logged at 180'. Hole was washed down with a 7 7/8" bit to 160', and cemented at 160' with 50 sacks, through the drill pipe. Hole was standing full of drilling mud. 50 sacks was now pumped, through 50' of drill pipe, circulating cement to the base of the cellar. This cementing was done by Halliburton Cementing Company. No salt was penetrated in the drilling of this surface hole.
I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/6/67

INV. NO. 5015-W

Signed: Archie Elving
Well Plugging Supervisor