

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JUL 7 1965
7-7-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name William H. Pine

Complete Address: McCulloch Bldg., Okmulgee, Oklahoma

Lease Name Robinson Well No. # 1

Location C NW NE Sec. 5 Twp. 31 Rge. 18 (E) (W) W

County Comanche Total Depth 2241'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: This was a lost hole

Plugging Contractor: Hellar Drilling Company, Inc.

Address: 1014 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 4:00 PM Day 5th Month July Year 1965

The Above well was plugged as follows:

509' of 8 5/8" surface pipe, cement circulated with 350 sacks. Circulation was lost, and several squeeze jobs were attempted but failed. On the last squeeze job the cement was never drilled out, and the top of the cement was at 525' in the hole. The hole was standing full of mud. 1st cementing plug and 1/4 sack of hulls was pushed in fluid to 350', and cemented with 35 sacks, through the drill pipe. Hole was filled with mud to 40', 2nd cementing plug, bridged solid with hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks. This cementin
was done by Sun Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/7/65

INV. NO. 1427-W