

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

REV. 03/72

CPA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-033-209400000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Helmerich & Payne, Inc. KCC LICENSE # 5293 ^{6/98}
(owner/company name) (operator's)

ADDRESS 2606 Fleming CITY Garden City

STATE Kansas ZIP CODE 67846 CONTACT PHONE # (316) 276-3693

LEASE Brass WELL# 1-8 SEC. 8 T. 32 R. 18 (East/West) (West)

W/2 - W/2 - NE - SPOT LOCATION/QQQQ COUNTY Comanche

1320 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2310 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL DEA SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE 20 SET AT 40 CEMENTED WITH 4 yds. Redimix SACKS

SURFACE CASING SIZE 8 5/8 SET AT 698 CEMENTED WITH 425 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 6068 CEMENTED WITH 350 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5776-5788', 5082-5096', 5035-5043', 4400-4408'
CLBP @ 5740', CLBP @ 5064', CLBP @ 4500'

ELEVATION 2142/2156 T.D. 6088 PSTD 6019 ANHYDRITE DEPTH 1860
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING All cmt. is 60/40 Poz, 6% gel. Sand back to 4350'. Cap w/5 sks

cmt. 40 sks @ 1000', 50 sks @ 700', 40 sks @ 300' and 10 sks @ 40'. Per Richard Lacey

10-23-97

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? 10-28-1997

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ken Jehlik PHONE# (316) 276-3693

ADDRESS 2606 Fleming Garden City City/State Kansas

PLUGGING CONTRACTOR Allied Cementing KCC LICENSE # _____
(company name) (contractor's)

ADDRESS Medicine Lodge, Ks. PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10-24-97 AUTHORIZED OPERATOR/AGENT: Ken Jehlik
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

October 28, 1997

Helmerich & Payne Inc
2606 Fleming
Garden City KS 67846

Brass #1-8
API 15-033-20,940-00-00
1320 FNL 2310 FEL
Sec. 08-32S-18W
Comanche County

Dear Ken Jehlik,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760