

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 5-033-20703-200-01 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Service Drilling Co. OPERATORS LICENSE NO. 05987

ADDRESS 1800 Fourth National Bank Bldg. Tulsa OK 74119 PHONE # (918) 582-9141

LEASE (FARM) Gates WELL NO. 1 WELL LOCATION NW NW COUNTY Comanche

SEC. 19 TWP. 32S RGE. 18W or (W) TOTAL DEPTH 5805' PLUG BACK TD 5278'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8 SET AT 507' CEMENTED WITH 208 SACKS

CASING SIZE 4 1/2 SET AT 5278' CEMENTED WITH 275 SACKS

PERFORATED AT 5245'-5258'; CIBP @ 4910'; 4303'- 4307'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Load hole w/9# mud, 36 vis mud. Spot 20 sx cmt plug @ 4300'. Cut 4 1/2" casing at 3600'±. Pull casing. Spot 50 sx cement plug from 560' - 460' Spot 10 sx cement plug from 40' - 5 GL; all plugs separated by 9# mud. Cut off 8 5/8" @ -3 GL.

Weld on plate with well info.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? attached
(if not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 15, 1987

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike Barnhart or Mark Pulver PHONE # (918) 582-9141

ADDRESS 1800 Fourth National Bank Bldg. Tulsa OK 74119 RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1987

PLUGGING CONTRACTOR Sargents Casing Pulling LICENSE NO. 6547 6/87

ADDRESS Box 506 Liberal KS 67901 CONSERVATION DIVISION PHONE # (316) 624-7455
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Mike Barnhart
(Operator or Agent)

DATE: 5-7-87

①

State of Kansas



15-033-20703-00-01

Mike Hayden
Keith R. Henley
Rich Kowalewski
Margalee Wright
Judith A. McConnell

Governor
Chairman
Commissioner
Commissioner
Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

AUG 11 '87

EXPIRES

May 11, 1987

WELL PLUGGING NOTICE

Gates #1
NW NW
Sec. 19-32S-18W
Comanche County

Service Drilling Company
1800 Fourth National Bank Bldg.
Tulsa, OK 74119

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
Acting Director
State Corporation Commission

Please contact the district office to review your suggested method of plugging
DIST. #1 302 West McArtor, Dodge City, KS 67801 (316) 225-6760
five days prior to plugging the well (KAR-82-3-113).