

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20,483-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Tera Resources Inc.

Complete Address P.O. Box 839, Oklahoma City Okla 73101

Lease Name Kirk Well No. 1

Location SE-SE-SE Sec. 8 Twp. 31 Rge. 19 (East)(West)

County Comanche Total Depth 6039'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was equipt but never produced

Plugging Contractor Astro Well Service

Address Woodward Okla License No.

Operation Completed: Hour: 2:45 PM Day: 25 Month: May Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 5310' of 5 1/2" production pipe & cemented it with 475 lbs of cement. The top of cement outside 5 1/2" pipe was at 3000'. They plugged the 5 1/2" back to 5276' then perforated it at 5128' to 40' & 5149' to 63' & 3279' to 83'. 1st plug cemented bottom to cover perforations with flakes & 60 lbs of cement. Then 2nd plug at 3190' with 40 lbs of cement. 3rd plug at 1050' with 80 lbs of cement. 4th plug at 60' with 20 lbs of cement. They pumped the cement through tubing with hole full of fluid. They wire

Amount of Surface Casing: 1031' of 8 1/8" cement circulated with 300 lbs of cement. (over)

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luther
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1982
06-02-1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

6-1-82
3/2-w

lined every plug to see if cement stayed. They
recovered 2866' of 5½" production pipe. The plugging
was accomplished by Allied Cementing.