

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20528-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name X.R.M. Petroleum Corp

Complete Address 817 17th St. Suite 820 Denver Colo 80202

Lease Name Bird Well No. 1-32

Location C-NE-SW Sec. 32 Twp. 31 Rge. 19 (East)(West)

County Comanche Total Depth 5460'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was completed ^{Produced} ~~fractured~~

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase Kansas 67524 License No. 681

Operation Completed: Hour: 9:30 AM Day: 6 Month: Aug Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 5303' of 4 1/2" production pipe & perforated the pipe from 4874' to 80'. 1st plug sand bottom back to 4825' & dumped 4 sks of cement on sand with below. 2nd plug pumped through 8 5/8" head. They pumped 5 sks shells 2.5 sks gell & released rubber plug & followed it with 150 sks of cement. The plugging was accomplished by allied cementing.

Amount of Surface Casing: 803' of 8 5/8" circulated with 250 sks cement

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luther
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
08-10-1982
AUG 10 1982
CONSERVATION DIVISION
Wichita, Kansas

DATE 8-13-82
WELL NO. 892-W