

M
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1963
5-13-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ashland Oil & Refining Co.

Complete Address: Box 949, Liberal, Kansas

Lease Name Lawrence York Well No. # 1

Location C SE NW Sec. 6 Twp. 32 Rge. 17 (E) (W) W

County Comanche Total Depth 5981

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gale E. Toland Casing Pulling Co.

Address: Box 4336, Oklahoma City, Oklahoma License No. 246 (old no.)

Operation Completed: Hour 3:00PM Day 9th Month May Year 1963

The Above well was plugged as follows:

570' fo 8 5/8" surface pipe, cement circulated with 625 sacks, 5200' of
4 1/2" long string, cemented with 175 sacks. Plugged back to 5171'. Perfer-
ated 5140' to 23'. Sanded to 5100', cemented with 10 sacks. Hole was
filled with mud to 250', 10' rock bridge, cemented with 20 sacks, with
pump truck. Hole was filled with mud to 40', 10' rock bridge, cemented
with 10 sacks, with pump truck, to base cellar.

4225' of 4 1/2" long string recovered from hole

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/13/63
INV. NO. 7054-W

Signed: Archie Elving
Well Plugging Supervisor