

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-21-79
DEC 21 1979
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -007 - 20776-0000 (of well)

Operator's Full Name Carl Todd

Complete Address 1117 West River Bend, Wichita, Ks. 67203

Lease Name Levens Well No. 1-2

Location NW NW SE Sec. 2 Twp. 30S Rge. 13 (E) (W) X

County Barber Total Depth 4735

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn's Casing Pulling Inc.

Address Box 413, Ellinwood, Ks. 67526 License No. 832

Operation Completed: Hour 2:45 Pm. Day 19 Month 12 Year 1979

The above well was plugged as follows:

224' 10 3/4" casing. 4 1/2" casing set at 2915' w/75 sax cement. PB to
2916'-Pref's at 2825' & 2802'-Sand back to 2775' top sand w/ 4 sax
mixed cement w/dump bailer. Pull 2136' 4 1/2" casing. Howco mixed &
pumped 8 sax hulls-25 sax gel-175 sax 50/50 posmix cement w/4% gel &
3% cc. to top of casing. Shut in w/400# pressure.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bill Owen
Well Plugging Supervisor

DATE 12-21-79

INV. NO. 1170-w