

To: 1 040980. 7-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

20810
API NUMBER 15- 033-20,910 -0000
NE NE NE, SEC. 13, T 31 S, R 19 W/4
4770 feet from S section line
475 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6006
Operator: Molz Oil Company
Name & Address: RR 2, Box 54
Kiowa, KS 67070-0074

Lease Name Pauline Well # 1A
County Comanche 169.65
Well Total Depth 5220 feet
Conductor Pipe: Size 13 3/8 feet 232
Surface Casing: Size 8 5/8 feet 632

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1:30 p.m. Day: 6 Month: 7 Year: 1995

Plugging proposal received from Alan Vratle
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5219', PBTD 5151', Perfs at 4951-52, 5140-48'
1st plug sand back to 4900' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 2 p.m. Day: 6 Month: 7 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4900' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 200 psi. 8 5/8" had been cemented w/125 sx on bottom.
Baskets were run at 175' and 215' and top cemented back to surface with 54 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED
DATE 7-19-95
INV. NO. 43104

Signed *Stephen J. [Signature]*
(TECHNICIAN)

RECEIVED
CORPORATION COMMISSION
JUL 1 1995
WICHITA, KANSAS