

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21032-00-00  
Spot: CSESE Sec/Twnshp/Rge: 17-31S-19W  
420 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: SWAYZE TWIN Well Number: 1  
County: COMANCHE Total Vertical Depth: 5248 feet

Operator License No.: 30407  
Op Name: BLACK PETROLEUM COMPANY  
Address: PO BOX 12922  
WICHITA, KS 67277

Conductor Pipe: Size 13.375 feet: 302  
Surface Casing: Size 8.625 feet: 679 WITH 285 SX CMT  
Production: Size 5.5 feet: 5247 WITH 125 SX CMT  
Liner: Size feet: 170.56

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2000 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1100' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR GEL SPACER.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/15/2000 11:15 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SAND BACK TO 4860' AND 5 SX CMT. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1100' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USED 15 SX GEL FOR GEL SPACER.

RECEIVED  
STATE CORPORATION COMMISSION  
12-19-2000  
DEC 19 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4000' OF 5 1/2' CASING.

Plugged through: CSG

District: 01

Signed Steve Durrant  
(TECHNICIAN)

INVOICED  
DATE 12/20/00 DEC 18 2000  
INV. NO. 2001061154 MP