

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21133-00-00  
Spot: S2SWNW Sec/Twnshp/Rge: 5-32S-17W  
2310 feet from N Section Line, 610 feet from W Section Line  
Lease/Unit Name: BRASS Well Number: 1-5  
County: COMANCHE Total Vertical Depth: 5680 feet

Operator License No.: 31120  
Op Name: PELICAN HILL OIL & GAS, INC.  
Address: 1401 N EL CAMINO REAL, STE 207  
SAN CLEMENTE, CA 92672

Conductor Pipe Size: 20 feet: 75  
Production Casing Size: 5.5 feet: 5331 WITH 125 SX CMT  
Surface Casing Size: 8.625 feet: 684 WITH 325 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/29/2003 11:30 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 5075' WITH 2 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/29/2003 2:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5287'. PERFS AT 5130-40'. CIBP @ 5075' WITH 2 SX CMT. PUMPED 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 100#. SHUT IN PRESSURE 100#.

RECEIVED  
7-8-03  
SEP 08 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3400' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
SEP - 3 2003  
KCC Dodge City

Signed

*[Signature]*

(TECHNICIAN)

INVOICED  
2-8-03  
INV. NO. 2004060485

Form CP-2/3