

1 070311

MAR 7 1987

API NUMBER 15- 033-20,705-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E/2 E/2 NE, SEC. 4, T 32 S, R 17 W/8

3960 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name McCay "A" Well # 1

Operator: TXO Production Corporation

County Comanche 182.00

Name & Address 155 North Market, Suite 1000

Well Total Depth 5200 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 520

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 12:10 p.m. Day: 7 Month: 3 Year: 19 87

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2080' Anhydrite 939-70'

1st plug at 970' with 50 sx cement, 2nd plug at 550' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 10 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 p.m. Day: 7 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 970' with 50 sx cement,

2nd plug at 550' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 10 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 3-20-87

Signed Dan Goodrow (TECHNICIAN)

MAR 18 1987 3-18-87 CONSERVATION DIVISION Wichita, Kansas

INV. NO. 16367

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date February 26, 1987 month day year 1987

API Number 15-033-20,705-0000

OPERATOR: License # 5171 Name TXO Production Corp. Address 155 N. Market, Suite 1000 City/State/Zip Wichita, Kansas 67202 Contact Person Cory West Phone (316) 269-7655

E/2 E/2 NE Sec. 4 Twp. 32 S, Rg. 17 West 3960' Ft. from South Line of Section 330' Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5380 Name Eagle Drilling, Inc. City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 330' feet County Comanche Lease Name McCAY 'A' Well # 1 Ground surface elevation (2080') feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 100' Depth to bottom of usable water 200' Surface pipe planned to be set 500' Projected Total Depth 5200' feet Formation Mississippian

Well Drilled For: Well Class: Type Equipment: Oil SWD Infield Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 2-20-87 Signature of Operator or Agent Cory West Title Drlg. & Prod. Engineer

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. This Authorization Expires 8-23-87 Approved By 2-23-87 Spod 2-25-87 Form C-1 6/85

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth (e.g., ±5100'), feet depth with, size of casing (e.g., 11), and material (Econolite). Includes a row for (2) Rathole with 10' depth and 10' mousehole.

Handwritten notes: PUSHER Butch Strenert, TD 5200 FORMATION MUD, SURFACE PIPE 8 5/8" @ 520', ANHYDRITE 939'-970', ELEVATION 2080', STARTING TIME & DATE 3-7-87 12:10 PM, COMPLETION TIME & DATE 3-7-87 2:30 PM, 1st PLUG @ 970 FT. W/ 50 SX, 2nd PLUG @ 550 FT. W/ 40 SX, 3rd PLUG @ 40 FT. W/ 10 SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ 10 SX, MOUSE HOLE CIRCULATED W/ 10 SX, WATER WELL PLUGGED W/ B.G. 60/40/60, CEMENT COMPANY D.G., TECHNICIAN D.G.

STATE CORPORATION COMMISSION 3-18-87 MAR 18 1987 CONSERVATION DIVISION