

1 010193

DEC 2 2 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,956-A-00-01
SE SW SE, SEC. 2, T 30 S, R 13 W/E
330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Lawrenz Well # 1-2

Operator: F.G. Holl Estate
Name &
Address 6427 E. Kellogg
Wichita, KS 67207

County Barber 153.56

Well Total Depth 4725 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 210

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:30 p.m. Day: 22 Month: 12 Year: 19 86

Plugging proposal received from Fred Mease

(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 4 1/2" at 2867' PBSD 2875' Perfs at 2781-83', 2784-88' Elevation 1923'KB

1st plug pump 1 sx hulls, 20 sx cement, release 4 1/2" wiper plug - displace '2650'

2nd plug pump 2 'sx hulls 15 sx gel, 70 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Don Ubel and Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 22 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls, 20 sx cement, plugged at 2650' with wire line,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.

STATE CORPORATION COMMISSION
12-30-86
DEC 30 1986

Maximum pressure 300 psi and shut in 200 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel by Halliburton. Recovered 1528' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did ~~not~~ observe this plugging.

Signed *Paul Luthi*
(TECHNICIAN)

DATE 12-31-86

INV. NO. 15694