

1080111

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007- 21,272-~~0000~~

SW NE NW , Sec. 2 , T 30 S, R 13 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Eckles Well # 3-2

Operator: F. G. Holl
Name & 6427 East Kellogg, Wichita, KS 67207
Address

County Barber

Well Total Depth 4586 feet 149.05

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:00 pm Day: 5 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 2960 PBTD 2950

1st plug pump 30 sx cement on bottom and stop plug at 1800' 3200# pressure

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack

hulls, and release 8 5/8" rubber plug and pump an additional 150 sx cement

Maximum pressure 700# and shut-in pressure 100#

Signed J. M. Fred
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:15 pm Day: 5 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 2960 PBTD 2950

1st plug pumped 30 sx cement on bottom and stopped plug at 1800' 3200# pressure

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack

hulls and released 8 5/8" rubber plug and pumped an additional 150 sx cement

Maximum pressure 700# and shut-in pressure 100#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 1714' of 4 1/2"