

1 010007

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,772 -00-01
NW SW NW SEC. 2, T 30 S, R 13 W/E
3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5035

Lease Name Tregellas Well # 5

Operator: Aladdin Petroleum Corp.

County Barber 150.48

Name & Address 809 Petroleum Building

Well Total Depth 4630 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 13 3/8" feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 am Day: 12 Month: July Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4628' Perfs at 4374-83'; 4383-88'; 4495-01'; 4501-03'; 4582-88'

1st plug sand back to 4325' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 13 3/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:15 am Day: 12 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4325' and dump 4 sx cement on top of sand

through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls, released 13 3/8" rubber plug and pumped 150 sx cement

Maximum pressure 300 psi and shut in 100 psi

Remarks: Recovered 2505' 4 1/2" casing. Used 60/40 Pzomxi 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

Signed Jack P. Luthi
(TECHNICIAN)

INVOICED
DATE 7-24-85
INV. NO. 9081

RECEIVED
STATE CORPORATION COMMISSION

7-22-85
CONSERVATION DIVISION

