

1 010004

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5035

Operator: Aladdin Petroleum Corp.
Name & Address 809 Petroleum Building
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:45 am Day: 12 Month: July Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4623' Perfs at 4368-76'; 4389-83'; 4407-15'; 4493-01'; 4501-03'

1st plug sand back to 4320' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 200 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:30 am Day: 12 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 4 sx cement on top of sand through bailer. 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 500 psi

Remarks: Recovered 3192' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied
(If additional description is necessary, use BACK of this form.)

(If ~~did~~ ~~not~~ observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED
DATE 7-24-85
INV. NO. 9082

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
7-22-85



RADIOACTIVITY LOG

COMPANY ALADDIN PETROLEUM CORPORATION WELL TREGELLAS #2 FIELD SAWYER County BARBER State KANSAS	COMPANY	ALADDIN PETROLEUM CORPORATION			
	WELL	TREGELLAS #2			
	FIELD	SAWYER			
	COUNTY	BARBER	STATE	KANSAS	
	Location	NE - NW - NW		Other Services:	
Sec.	2	Twp.	30S	Rge.	13W

Permanent Datum	GROUND LEVEL	Elev.	1793'	Elev. K.B.	1801'
Log Measured From	8	Ft. Above Perm Datum		DF	
Drilling Measured From	KELLY BUSHING			GL	1793'

Date	11-1-78	11-1-78
Run No	ONE	ONE
Type Log	GAMMA	NEUTRON
Depth—Driller	4610'	4610'
Depth—Welex	4602'	4602'
Bottom Logged Interval	4591'	4601'
Top Logged Interval	2600'	2600'
Type Fluid in Hole		STATE COR.
Salinity. PPM Cl.		
Density		
Level	DRY	
Max rec temp. deg F.		
Operating Rig time	2 HOURS	
Recorded By	J. JARMER	
Witnessed by	MR. CARPENTER	

REC'D
 MAY 29 1985
 5-29-85
 CONSERVATION DIVISION
 Wichita, Kansas

RUN No	BORE-HOLE RECORD				CASING RECORD		
	Bit	From	To	Size	Wgt.	From	To
1	12 1/4"	0	946'	3-5/8"		0	946'
2	7-1/8"	946'	4627'	4 1/2"		0	4623'