

To: 1 060151 12-14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,866 -00-00
C NE NW, SEC. 12, T 31 S, R 19 W/EX
660 feet from N section line
1980 feet from W section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Hadley "A" Well # 1
County Comanche 169.00
Well Total Depth 5200 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 688

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company License Number 5123
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 14 Month: 12 Year: 1992

Plugging proposal received from Doyle Folkerts

(company name) Pickrell Drilling Company (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1050'

- 1st plug at 1100' with 50 sx cement,
- 2nd plug at 720' with 50 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3 a.m. Day: 14 Month: 12 Year: 1992

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement,
2nd plug at 720' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)
I (XXXX) / did not observe this plugging.

INVOICED
DATE 1-8-93
INV. NO. 37156

Signed Case Morris 12-22-1992
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1992