

1 080517

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,762-~~cccc~~

SE NE NW, SEC. 2, T 30 S, R 13 W/E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Eckles Well # 2-2

Operator: F. G. Holl

County Barber 150.80

Name & Address 6427 E. Kellogg

Well Total Depth 4640 feet

Wichita, KS 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 190

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 29 Month: April Year: 19 86

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4639 1/2' PBTD 4502' Perfs at 4411-15'; 4423-27'

1st plug sand back to 4475' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls, release 10 3/4" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 pm Day: 29 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4475' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeeze well with 3 sx hulls, 15 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls, released 10 3/4" rubber plug and pumped 150 sx cement.

Maximum pressure 350 psi and shut in 0

Remarks: Recovered 3242' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (do not XXXXXX) observe this plugging.

DATE MAY 06 1986

Signed J. N. [Signature] (TECHNICIAN)

INV. NO. 13651

FORM CP-2/3 Rev. 01-84

RECEIVED
STATE CORPORATION COMMISSION
MAY 05 1986
5-5-86
CONSERVATION DIVISION
Wichita, Kansas

4-29