

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05576-00-02
Spot: S2NENW Sec/Twnshp/Rge: 11-11S-18W
990 feet from N Section Line, 1980 feet from W Section Line
Lease Name: FELDCAMP Well #: 1
County: ELLIS Total Vertical Depth: 3514 feet

Operator License No.: 33937
Op Name: NEAL LAFON REALTY INC. DBA MERI
Address: 1475 WARD DR
FRANKTOWN, CO 80116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	3.5	3500		225 SX
SURF	8.625	1201		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2014 9:45 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: BRTETT HILDEBRAND Company: RENEGADE WELL SERVICE LLC. Phone: (785) 726-3490

Proposed Plugging Method: Ordered 405 sx 60/40 pozmix 4% gel cement w/100 # hulls and 1 bag C.C.
1954- Well plugged. Pulled 850' of 5 1/2" casing.
2008- OWWO. Cemented in 3 1/2" liner.
PBTD-3499'
Perforations: 3473' - 3481'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2014 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 3 1/2" casing with a swedge and pumped 350 sx cement w/100 # hulls. Well went on hard vacuum. Left well to set for 1 hour. Ordered C.C. and more hulls. Rigged back onto 3 1/2" casing and pumped 50 sx cement w/1 bag C.C. to 725 psi and 700 psi shut in pressure. Rigged to 8 5/8" casing and pumped 5 sx cement w/100 psi and 100 psi shut in pressure.

GPS: 39.11485 -099.28946
4282' FSL 3419' FEL
SE SW NE NW

Perfs:

Top	Bot	Thru	Comments
3473	3481		

Remarks: GLOBAL CEMENTING CO (SOS) TICKET # 2169

Plugged through: CSG

KCC WICHITA

APR 23 2014

RECEIVED

District: 04

Signed


4/24/14
(TECHNICIAN)

CM

APR 17 2014