

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19084-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 16-14S-14W
367 feet from S Section Line, 3015 feet from E Section Line
Lease Name: COADY Well #: 1
County: RUSSELL Total Vertical Depth: 3155 feet

Operator License No.: 8996
Op Name: MID-CONTINENT RESOURCES, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3020		
PROD	7	3031		200 SX
SURF	10	280		200 SX

Well Type: EOR UIC Docket No: E08456.1 Date/Time to Plug: 04/02/2014 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: MID-CONTINENT RESOURCES Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2014 8:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 900' and 1600'. Ran tubing to 2911' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 350' and pumped 30 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped cement until pressure was achieved. Shut in. Hooked to braden head and pumped cement until pressure was achieved. Shut in.

GPS: 38.82820 -098.88384

Perfs:

Top	Bot	Thru	Comments
3031	3155		

KCC WICHITA

APR 17 2014

RECEIVED

Remarks: SWIFT SERVICES TICKET # 25414

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

4/24/14

cc to MC 4/17/14

Form CP-2/3

APR 07 2014