

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02634-00-00
Spot: NENW Sec/Twnshp/Rge: 11-14S-14W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BLEHM Well #: 5
County: RUSSELL Total Vertical Depth: 2434 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2434		
SURF	8.625	88		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2014 1:00 PM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: DAN Company: G L M Phone: (785) 483-1599

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2014 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2335' and pumped 115 sx cement. Pulled tubing to 1160' and pumped 115 sx cement. Circulated cement out braden head and backside. POOH. Hooked to casing and pumped 30 sx cement. Shut braden head and pumped until 500 psi was achieved. Shut in.

GPS: 38.85466 -098.84759

Perfs:

Remarks: QUALITY

Plugged through: DP

KCC WICHITA

APR 17 2014

RECEIVED

District: 04

Signed Ray A Dinkel
4/24/14 (TECHNICIAN)

CM

APR 07 2014

APR 07 2014