

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20668-00-00  
Spot: E2NENWNW Sec/Twnshp/Rge: 33-11S-22W  
4950 feet from S Section Line, 4260 feet from E Section Line  
Lease Name: FLAGLER Well #: 3  
County: TREGO Total Vertical Depth: 4055 feet

Operator License No.: 31819  
Op Name: CHOLLA PRODUCTION, LLC  
Address: 10390 BRADFORD RD. SUITE 201  
LITTLETON, CO 80127

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4055		200 SX
SURF	8.625	301		190 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2014 9:00 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: KELLY BRANUM Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 483-2662

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls. Shot perforations at 295', 1038', 1843' and 2478'. Perforations at 3952' - 3970'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/09/2014 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3210' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2150' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1125' and pumped 85 sx cement. Good circulation of cement out casing and back. Pulled tubing. Topped off casing with 15 sx cement.

GPS: 39.05854 -099.77534

Perfs:

Remarks: CONSOLIDATED CEMENTING TICKET # 47579

Plugged through: TBG

KCC WICHITA

APR 17 2014

RECEIVED

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

APR 18 2014

Form CP-2/3