

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-30103-00-01
Spot: SESENW Sec/Twnshp/Rge: 33-11S-22W
2310 feet from N Section Line, 2970 feet from E Section Line
Lease Name: FLAGLER Well #: 5
County: TREGO Total Vertical Depth: 4098 feet

Operator License No.: 31819
Op Name: CHOLLA PRODUCTION, LLC
Address: 10390 BRADFORD RD. SUITE 201
LITTLETON, CO 80127

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4092		200 SX
SURF	8.625	282		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2014 9:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: KELLY BRANUM Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 483-2662

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Shot perforations at 278', 1005', 1825' and 2450'.
Junk in hole at 1615'. Tried to mill on and could not make any more hole. Case Morris gave approval to plug at 1615'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2014 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1600' and pumped 245 sx cement w/no hulls. Good circulation of cement. Pulled tubing out and topped off with 15 sx cement. Tied on to back side and squeezed w/30 sx cement. Hole standing full.

GPS: 39.05301 -099.77061

Perfs:

Top	Bot	Thru	Comments
3976	3986		
3967	3986		
3640	3880		
3624			
3604			
3388			
1200			

Remarks: CONSOLIDATED TICKET # 47618

Plugged through: TBG

KCC WICHITA

APR 17 2014

RECEIVED

District: 04

Signed _____

(TECHNICIAN)

CM

APR 09 2014