

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21217-00-00
Spot: SESESW Sec/Twnshp/Rge: 33-11S-22W
330 feet from S Section Line, 2310 feet from W Section Line
Lease Name: FLAGLER Well #: 11
County: TREGO Total Vertical Depth: 4120 feet

Operator License No.: 31819
Op Name: CHOLLA PRODUCTION, LLC
Address: 10390 BRADFORD RD. SUITE 201
LITTLETON, CO 80127

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4118		215 SX
SURF	8.625	332		210 SX
T1	2.875	3973		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2014 10:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KELLY P BRANUM Company: ULTIMATE WELL Phone: (785) 324-1414

Proposed Plugging Method: Ordered 700 sx 60/40 pozmix 4% gel cement w/1000 # hulls.
Perforations at 3994' - 4018'
Shot perforations at 1080', 1885' and 2525'
CIBP at 3952'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2014 4:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3946' and pumped 125 sx cement w/250 # hulls. Pulled tubing to 2846' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 1916' and pumped 225 sx cement w/350 # hulls. Good circulation of cement. Pulled tubing out and topped off w/25 sx cement. Tied on to backside and squeezed w/90 sx cement and 150 # hulls.

GPS: 39.04588 -099.77071

Perfs:

Top	Bot	Thru	Comments
3994	4018		

KCC WICHITA

APR 23 2014


RECEIVED

Remarks: CONSOLIDATED CEMENT TICKET # 47621

Plugged through: TBG

District: 04

Signed


4/24/14
(TECHNICIAN)

CM

APR 15 2014