

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21457-00-00
Spot: SWSENW Sec/Twnshp/Rge: 34-9S-25W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WERTH A Well #: 1
County: GRAHAM Total Vertical Depth: 4086 feet

Operator License No.: 31000
Op Name: PRATER OIL & GAS OPERATIONS, INC.
Address: 906 WILLIAM WAY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4085		150 SX
SURF	8.625	230		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2014 11:30 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: CHEYENNE WELL SERVIC Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Perforations at 3842' - 3874' - 4045'.
Plugging Shot perforations at 225', 1345', 2180' and 2700'.
Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2014 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3700' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 2500' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1100' and pumped 156 sx cement. Good circulation of cement out of both the casing and backside. Pulled tubing out and topped off w/30 sx cement. Hole standing full.

GPS: 39.22711 -100.10191

Perfs:

Top	Bot	Thru	Comments
4045	4049		
4006	4016		
3982	3985		
3874	3876		
3842	3844		

KCC WICHITA

Remarks: ALLIED CEMENT TICKET # 62910

APR 17 2014

Plugged through: TBG

RECEIVED

District: 04

Signed [Signature]
4/24/14 (TECHNICIAN)

CM

APR 11 2014