

To: 1 051217
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-17
API NUMBER 15- 033-20,651-00-00
NE SE, SEC. 12, T 32 S, R 16 W/E
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Lease Name Einsel Well # B-1
County Comanche 158.08

Operator: Robinson Oil Company
Name & Address 300 West Douglas, Suite 420
Wichita, KS 67202

Well Total Depth 4864 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 224

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 17 Month: 10 Year: 19 89

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4860' PBT 4758' Perfs at 4765-67, 4737-40'
1st plug pump 200 lbs. hulls and 25 sx common cement on bottom,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Mike Spain
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 17 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx common cement and 200 lbs. hulls to 4600',
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released
10 3/4" wiper plug and pumped 125 sx cement.
Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If did / X did not) observe this plugging.

Signed Richard W. Loay
(TECHNICIAN)

DATE 10-24-89

INV. NO. 26200

RECEIVED
STATE CORPORATION COMMISSION
10-19-89
OCT 19 1989
CONSERVATION DIVISION
Wichita, Kansas