

1060213

TO: STATE CORPORATION COMMISSION API NUMBER 15-033-21,107 0000
60'S 160'W W/2 W/2 NW SEC. 1, T 32 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 1380 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 830 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME UNRUH WELL # 1-1

TECHNICIAN'S PLUGGING REPORT 7/25 COUNTY COMANCHE 186.94

OPERATOR LICENSE # 31120 WELL TOTAL DEPTH 5752 FEET

OPERATOR: PELICAN HILL OIL & GAS PRODUCTION CSG: SIZE " FEET

NAME AND 1401 N EL CAMINO REAL, STE. 203 SURFACE CASING: SIZE 8 5/8" @ 662' WITH SX

ADDRESS SAN CLEMENTE, CA 92672 207 CONDUCTOR CSG: SIZE 20" @ 40'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ABERCROMBIE RTD LICENSE NUMBER 30684

ADDRESS 150 N MAIN, STE 801, WICHITA, KS 67202-1383

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 25 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BILL CRAIG

(COMPANY NAME) ABERCROMBIE RTD (PHONE) 316-262-1841

WERE:

1ST PLUG AT 1000' WITH 50 SX CEMENT. 2ND PLUG AT 670' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 25 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1000' WITH 50 SX CEMENT. 2ND PLUG AT 670' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

RECEIVED STATE CORPORATION COMMISSION 08-04-2000 AUG 4 2000

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I DID NOT OBSERVE THIS PLUGGING.

DATE 8/10/00 SIGNED Michael J. Maier (TECHNICIAN) INV. NO. 1060338

FORM CP-2/3

CONSERVATION DIVISION Wichita, Kansas

Handwritten initials and signature in a circle.