

1051865

11-17

API NUMBER 15- 033-20,641-00-01

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW NW, SEC. 35, T 32 S, R 18 W/E

3690 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Kimble Well # 1

Operator: American Energies Corp.

County Comanche 186.55

Name & Address 155 N. Market, Ste. 710

Well Total Depth 5740 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 568

Abandoned Oil Well Gas Well ☒ Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Val Energy Inc. License Number 5822

Address P.O. Box 322, Haysville, KS 67060

Company to plug at: Hour: 10 a.m. Day: 17 Month: 11 Year: 19 94

Plugging proposal received from Todd Allam

(company name) Val Energy Inc. (phone) 316-522-1560

were: 5 1/2" at 5738' w/170 sx cement, PBTD 5724', Perfs at 5611-12'

Tubing cemented from 4831' to TD.

1st plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part None

Operations Completed: Hour: 10:45 a.m. Day: 17 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Richard M. Lacy (TECHNICIAN)

DATE 11-29-94

INV. NO. 41734

FORM CP-2/3
Rev. 01-84



AD
50-81

#1470

177

ORIGINAL

INVOICE DATE

03/19/91

DIRECT BILLING INQUIRIES TO:	TERMS	REMIT TO:
713-895-5821	NET AMOUNT DUE 30 DAYS FROM DATE OF INVOICE	B.J. SERVICES P.O. BOX 297476 HOUSTON, TX 77297

PAGE	INVOICE NO.
1	636575

AUTHORIZED BY
636575

PURCH. ORDER REF. NO.

AMERICAN ENERGIES CORPORATION

155 N. MARKET, SUITE 710
WICHITA KS 67202

WELL NUMBER : NA

#7200

CUSTOMER NUMBER :

2525 - 0

LEASE NAME AND NUMBER	STATE	COUNTY/PARISH	CITY	DISTRICT NAME	DISTR. NO.
KIMBLE	14	1407		Medicine Lodge	584
JOB LOCATION/FIELD	MTA DISTRICT		DATE OF JOB	TYPE OF SERVICE	
NA			03/19/91	LAND-SQUEEZE	

PRODUCT NUMBER	QUANTITY	DESCRIPTION	UNIT PRICE	U/M	EXTENDED PRICE
10102133	1.00	CEMENTING THRU TUBING 5,501 TO 6,0	1435.00		1,435.00
10107891	1.00	Fuel Surcharge	51.53		51.53
10109005	50.00	MILEAGE CHRG, FROM NEAREST BASE OF	2.35		117.50
10410504	100.00	CLASS "A" CEMENT	5.50	QT	550.00
10880001	100.00	MIXING SERVICE CHRG DRY MATERIALS,	1.10		110.00
10909810	1.00	SQUEEZE MANIFOLD	125.00		125.00
10940101	235.00	DRAYAGE, PER TON MILE	0.75		176.25
			SUBTOTAL		2,565.28
			DISCOUNT		452.48

Postel
4-8-91
[Signature]

ACCOUNT	1.0000% BARBER 4.2500% KS-NEW WELL	451.00 451.00	4.51 19.17
TAX EXEMPTION STATUS:		RECEIVED STATE CORPORATION COMMISSION SEP 21 1994 WICHITA KANSAS	
		PAY THIS AMOUNT	