

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-00099-00-01  
Spot: CSEnw Sec/Twnshp/Rge: 36-32S-18W  
1980 feet from N Section Line, 2130 feet from W Section Line  
Lease/Unit Name: PARCEL OWWO Well Number: 1-36  
County: COMANCHE Total Vertical Depth: 5784 feet

Operator License No.: 5254  
Operator Name: MIDCO EXPLORATION, INC.  
Address: 414 PLAZA DRIVE #204  
WESTMONT, IL 60559

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 281  
Production: Size 4.5 feet: 5769 187.98  
Liner: Size \_\_\_\_\_ feet:

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/23/2000 3:00:00 PM  
Plug Co. License No.: 31646 Plug Co. Name: DOUBLE T TOOL & SUPPLY D.B.A. JET WELL SVS.  
Proposal Rcvd. from: DAVE MAYFIELD Company: MIDCO EXPLORATION Phone: (630) 655-2198

Proposed Plugging Method: CIBP @ 4900 WITH 2 SX CMT. 1ST PLUG AT 1000' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG  
Date/Time Plugging Completed: 10/23/2000 4:35 PM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PERFS AT 5106-10, 5012-22, 5004-09, 4964-69. SET CIBP @ 4904' WITH 2 SX CMT. 1ST PLUG AT 1012' WITH 50 SX CMT. 2ND PLUG AT 311' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4225' OF 4 1/2" CASING.

Plugged through: TBG

OCT 31 2000  
10-31-2000  
CONSERVATION DIVISION  
Wichita, Kansas

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
DATE 11/1/00  
INV. NO. 2001060914

OCT 26 2000

Form CP 2/9