

Tax I 090871
STATE CORPORATION COMMISSION 10-28
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-033-20,944 -00-00
30' S & 100' W of
SW NE SW, SEC. 33, T 32 S, R 18 W, XX
1620 feet from S section line
1550 feet from WX section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3869
Operator: Imperial Oil Properties, Inc.
Name:
Address 212 N. Market, Ste. 513
Wichita, KS 67202-2013

Lease Name Bremer A Well # 33-1
County Comanche 192.99
Well Total Depth 5938 feet
Conductor Pipe: Size 20 feet 60
Surface Casing: Size 8 5/8 feet 646

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____
Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202
Company to plug at: Hour: 1:30 p.m. Day: 28 Month: 10 Year: 19 97
Plugging proposal received from Joe

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331
were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1050' with 50 sx cement, 2nd plug at 670' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 3:30 p.m. Day: 28 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1050' with 50 sx cement,
2nd plug at 670' with 50 sx cement,
3rd plug at 40' with 10 sx cement, 10-30-1997
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (XXXX) did not observe this plugging.
DATE 11-4-97
INV. NO. 49422

Signed [Signature] (TECHNICIAN)

RECEIVED
KANSAS CORP. COMM
OCT 30 4 12:23