

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92
RECEIVED
KANSAS CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

AUG 08 1994

8-8-94

API # 15-033-20,107-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE GRIFFITH "B" WELL# 1 SEC. 3 T. 31S R. 18 (XXXX/West)

- C - NE - SW SPOT LOCATION/QQQQ COUNTY COMANCHE

1980 FEET (in exact footage) FROM (S)X (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM X(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 541' CEMENTED WITH 400 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5128' CEMENTED WITH 160 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4953-4976, 4986-4990, 5002-5006

ELEVATION 2105' / -- T.D. 5130' PBDT 5020' ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU SARGENTS CASING PULLERS. TIH W/ 1-1/4" TBG TO 5006'. CIRC HOLE W/9 PPG MUD. SPOT 10 SXS CMT PLUG FROM 4903-5006'. DISPLACE W/220 GALS 9 PPG MUD. TOH W/TBG. PULL ON 4-1/2" CSG, LOCATE FREE POINT AND SHOOT OFF. SPOT 35 SXS CMT PLUG AT CUT OFF POINT. PULL 4-1/2" CSG TO 591'. SPOT 35 SXS CMT PLUG FROM 591-491'. TOH W/4-1/2" CSG AND SPOT 15 SX CMT PLUG FORM 53-3'. CUT OFF 8-5/8" CSG 3' BELOW GROUND LEVEL AND CAP. INSCRIBE WELL NAME, NUMBER, LEGAL DESCRIPTION AND PLUGGING DATE ON CAP. RDMO CSG PULLERS AND RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? YES

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

JERRY RUTTMAN PHONE# (316) 629-4382

ADDRESS P.O. BOX 351 City/State LIBERAL, KANSAS

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7/29/94 AUTHORIZED OPERATOR/AGENT: Dawid Kappeler for J. Ashton
J.L. ASHTON (signature) DIV. PROD. MGR.

8/94

1/95

D



Kansas Corporation Commission

Joan Finney, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

August 15, 1994

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Griffith "B" #1
API 15-033-20,107-0000
1980.FSL 1980 FWL
Sec. 03-31S-18W
Comanche County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760