

To: ✓ 1 040661
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-12
API NUMBER 15- 033-01,008-~~00-01~~ 1630

NW NW NW, SEC. 32, T. 31 S, R 18 W/E
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050
Operator: Hummon Corporation
Name:
Address 200 W. Douglas, Suite 1020
Wichita, KS 67202

Lease Name Boisseau Well # 1 WP
County Comanche
Well Total Depth 5170 168.0² feet
Conductor Pipe: Size 20" feet 145
Surface Casing: Size 13 3/8" feet 437

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:45 a.m. Day: 12 Month: 5 Year: 19 92

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4174.6' w/150 sx cement, PBTD 5134', Perfs at 5014-22'
1st plug bailer stuck in hole at 2200', 50' sand and 5 sx cement at that point,

2nd plug pump 2 sx hulls, 10 sx gel, 75 sx cement, 15 sx gel, 2 sx hulls, fill 450' to surface.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a.m. Day: 12 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded from 5134-4960', bailer hung in hole at 2000'. Wiped
line out of bailer. Put 50' of sand on top of bailer hung in hole with 5 sx cement on top of
sand bridge,

2nd plug pumped down 13 3/8" surface pipe with 200 lbs. hulls, 10 sx gel, 70 sx cement, 15
sx gel, 200 lbs. hulls and 250 sx cement.

Maximum pressure 650 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 600' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 5-22-92

INV. NO. 35320

Signed Stephen J. Tojano
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1992
CONSERVATION DIVISION
Wichita, Kansas