

1 060972

JUN 23 1987

15-033-20488-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Completion date 6/11/87
^{NW}
C SW NE, SEC. 32, T 31 S, R 18 W/X
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Lease Name Boisseau Well # 1

Operator: Molz Oil

County Comanche 186.39

Name & Address RR 2, Box 54

Well Total Depth 5735 feet

Kiowa, KS 67070

Conductor Pipe: Size _____ feet

Surface Casing: Size 13 3/8 feet 345

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10:30 a.m. Day: 23 Month: 6 Year: 19 87

Plugging proposal received from Elmo Morganstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5096' PBD 4750' Perfs at 5002-5006, 4686-92'

1st plug sand back to 4630' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release wiper plug and pump 150 sx cement.

Plugging Proposal Received by Glenn Barlow & Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 23 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4630' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

wiper plug and pumped 150 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 550 psi and shut in 225 psi.

JUN 30 1987

6-30-87

CONSERVATION DIVISION

Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2850' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

(if applicable) observe this plugging.

DATE 7-1-87

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 17398