

To: 1 090245 12-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,867-0000 107R
C NW SW, SEC. 31, T. 31 S, R 18 W/E
1980 feet from S section line
660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Buhl "A" Well # 1
County Comanche 169.00
Well Total Depth 5200 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 646

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 12:15 a.m. Day: 30 Month: 12 Year: 19 92

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427
were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1000'

1st plug at 1050' with 50 sx cement, 2nd plug at 670' with 50 sx cement,
3rd plug at 380' with 30 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:15 a.m. Day: 30 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1050' with 50 sx cement,
2nd plug at 670' with 50 sx cement,
3rd plug at 380' with 30 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(XXXX/ did not) observe this plugging.

DATE 1-14-93
INV. NO. 37206

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1993
1-6-93

FOR USE ONLY

EFFECTIVE DATE: 12-14-92

DISTRICT # 1

YES NO

POSS Circulation Area.

15-033-20, 867-0000 (Suggests for conductor) FORM MUST BE TYPE
State of Kansas FORM MUST BE SIZE
NOTICE OF INTENTION TO DRILL
ALL SUBJECTS MUST BE FILLE

Must be approved by the K.C.S. five (5) days prior to commencing well

Expected Spud Date 12 month day year
12 14 92
East: NW 31. Sec 31. Twp 31. S. Rg 18. X West:

OPERATOR: License # 5123 ✓
Pickrell Drilling Co. Inc.
Name: Pickrell Drilling Co. Inc.
Address: 110 N. Market, Suite 205
City/State/Zip: Wichita, Kansas, 67202
Contact Person: Larry J. Richardson
Phone: 262-8427

CONTRACTOR: License # 5123 ✓
Pickrell Drilling Co. Inc.
Name: Pickrell Drilling Co. Inc.

Well drilled for: Well class: Type Equipment:
Oil Infield X Mud Rotary
Gas Storage X Pool Ext. Air Rotary
Other Disposal Wildcat Cable
Seismic: # of Holes Other
Other
If OWD: old well information as follows:

Operator:
Well Name:
Comp. Date:
Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

ASPIRANT

Exp. 6/9/93
The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. sec.

Pusher Boyle Folkert
SPUD DATE 12-15-92 INIT. 92
LENGTH SURFACE PLANNED 690'
RESERVE PIT STATUS - REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHLED AHEAD? Y N
SURFACE PIPE 8 1/2" @ 6 1/2" CONDUCTOR
ANHYDRITE L- B-1000 ELEVATION
RAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1050 Ft. W/ SX
1/2 Base Anyh. @ 380 Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 670 Ft. W/ SX
40' Plug @ 70 Ft. W/ SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL Kilmory SX (Tvr. Well Pond Hauling)
TECHNICIAN 9m DATE 12-28-92
TYPE OF CEMENT 60/140 670
STARTING TIME 12:15 (AM/PM) DATE 12-30-92
COMPLETION TIME 1:15 (AM/PM) DATE 12-30-92
CEMENT COMPANY
RECEIVED
STATE REGULATION COMMISSION
1-6-1993