

1070138

TO: STATE CORPORATION COMMISSION

API NUMBER 15-033-20,468-0003  
NW NE NW SEC. 36, T 31 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DELANEY WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE 169.91

OPERATOR LICENSE # 5893 6/27 WELL TOTAL DEPTH 5228 FEET

OPERATOR: PRATT WELL SERVICE, INC. PRODUCTION CSG: SIZE 4 1/2" @ 5226' WITH 150 SX

NAME AND PO BOX 847 SURFACE CASING: SIZE 8 5/8" @ 268' WITH 300 SX

ADDRESS PRATT, KS 67124 CASING LINER : SIZE " W/ SX

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE, INC. LICENSE NUMBER 5893

ADDRESS PO BOX 847 PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 27 MONTH: 06 YEAR: 2000 RECEIVED STATE CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED FROM TOM ROSE

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531 JUN 30 2000 6-38-00

WERE: PERFS AT 5143-49, 5034-38, 4986-88 CONSERVATION DIVISION Wichita, Kansas

1ST PLUG CIBP AT 4950' WITH 2 SX CEMENT. 2ND PLUG SPOT 50 SX CEMENT AT 1080', GEL SPACER.

3RD PLUG SPOT 40 SX CEMENT AT 294'. 4TH PLUG SPOT 10 SX CEMENT AT 0-40'. GOOD CIRCULATION.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  X PART  NONE

OPERATIONS COMPLETED: HOUR: 6:00 PM DAY: 27 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG CIBP @ 4950' WITH 2 SX CEMENT. 2ND PLUG SPOT 50 SX CEMENT AT 1080'. GEL SPACER.

3RD PLUG SPOT 40 SX CEMENT AT 294'. 4TH PLUG SPOT 10 SX CEMENT AT 0-40'. GOOD CIRCULATION

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1102' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 7/5/00 SIGNED

(TECHNICIAN)

FORM CP-2/3

WELL NO. 1060012