

3-13

195 R

1 040529

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,046-0000
50' S of C SW NW, SEC. 2, T 31 S, R 18 W EX

3250 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lense Name Unruh "C" Well # 1

Operator: Graham-Michaelis Corporation
Name & Address: P.O. Box 247
Wichita, KS 67201

County Comanche 168.38
Well Total Depth 5181 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 971

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 13 Month: 3 Year: 19 91

Plugging proposal received from Dave Patterson

(company name) Graham-Michaelis (phone) 405-256-6491

were: 4 1/2" at 5180' w/100 sx cement, PBSD 5150', Perfs at 5028-48'

1st plug sand back to 4975' and dump 4 sx cement on top of sand through bailer, RECEIVED

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, STATE CORPORATION COMMISS

release 8 5/8" wiper plug and pump 150 sx cement.

MAR 20 1991
3-20-91
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 13 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4975' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2807' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (crossed out) observe this plugging.

Signed Stephens J. Pfeiffer (TECHNICIAN)

DATE APR 02 1991
INV. NO. 31270