

To: 1 041224
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-033-20,608-0000
C SW NE, SEC. 4, T 31 S, R 18 W X
3300 feet from S section line
1980 feet from E section line

12-13

TECHNICIAN'S PLUGGING REPORT
Operator License / 5134
Operator: Graham-Michaelis Corporation
Name:
Address: P.O. Box 247
Wichita, KS 67201

Lease Name Unruh Well # 4-4
County Comanche
Well Total Depth 5085 165.26 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 618

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 12:30 p.m. Day: 13 Month: 12 Year: 1996

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5084' w/150 sx cement, Perfs at 4800-5038' (5 sets)

1st plug pump 300 lbs. hulls and 20 sx cement, Loaded hole with mud and spotted plugs through 4 1/2":

2nd plug at 1000' with 50 sx cement,

3rd plug at 630' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4 p.m. Day: 13 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 300 lbs. hulls and 20 sx cement, Loaded hole with drilling mud and spotted plugs through 4 1/2" casing:

2nd plug at 1000' with 50 sx cement,

3rd plug at 630' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 4026' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE JAN 02 1997
OBSERVE THIS PLUGGING.

Signed Stephen J. Penfer (TECHNICIAN)

INV. NO. 47219
12-13