

1 121057

8-1-

15-033-20064-0000

API NUMBER 15-Completion date 5/20/70

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

C SW SE, SEC. 4, T 31 S, R 18 W/E  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Unruh Well # 2-4

Operator: Graham-Michaelis Corporation

County Comanche

Name & Address P.O. Box 247  
Wichita, KS 67201

Well Total Depth 5140 16705 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 599

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 8:30 a.m. Day: 1 Month: 8 Year: 19 95

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

logs: 4 1/2" at 5139' w/125 sx cement. Perfs at 5046-48, 5030-34'

1st plug pump 100 lbs. hulls and 20 sx cement, push plug to 4900',

2nd plug at 1000' with 50 sx cement,

3rd plug at 640' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 3 p.m. Day: 1 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. hulls and 20 sx cement, pushed plug to 4900',

2nd plug pumped 50 sx cement at 1000',

3rd plug pumped 50 sx cement at 640',

4th plug pumped 10 sx cement at 40'.

RECEIVED STATE CORPORATION COMMISSION

AUG 03 1995

8-3-95

CONSERVATION DIVISION WICHITA, KANSAS

Remarks: Used common cement by Sargent's. Recovered 3230' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 8-15-95

INV. NO. 43309