

To: ¹ 051539
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

41 API NUMBER 15-033-20,627-00-00 85
C SW, SEC. 33, T. 32 S, R. 16 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 4526
Operator: Evergreen Operating Corporation
Name & Address: 1512 Larimer St., Ste. 1000
Denver, CO 80208

1320 feet from S section line
3960 feet from E section line
Lease Name Davis Well # 1-33
County Comanche
Well Total Depth 5087 165.32 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 502

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Reeves Casing, Inc. License Number 30363
Address P.O. Box 94204, Oklahoma City, OK 73143

Company to plug at: Hour: 9:30 a.m. Day: 1 Month: 4 Year: 19 92

Plugging proposal received from Bob Reeves
(company name) Reeves Casing, Inc. (phone) 405-677-8347

ware: 4 1/2" at 5040' w/185 sx cement, PBTD 5035', Perfs at 4973-80'
1st plug set CIBP at 4900' with 1' sx cement on top,
2nd plug pump 50 sx cement at casing cut,
3rd plug set 50 sx cement at base of surface,
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 1 Month: 4 Year: 19 92.

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4900' with 1' sx cement on top,
2nd plug pumped 30 sx cement at 3190',
3rd plug pumped 50 sx cement at 530',
Hole did not circulate, tagged plug at 438',
4th plug pumped 10 sx cement at 40'.

RECEIVED
STATE CORPORATION COMMISSION
APR 07 1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3206' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-28-92
INV. NO. 35082

Signed Richard W. Lucy (TECHNICIAN)