

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21066-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 19-32S-16W
1375 feet from S Section Line, 1300 feet from W Section Line
Lease/Unit Name: THOMISON Well Number: 1-19
County: COMANCHE Total Vertical Depth: 5205 feet

Operator License No.: 30288
Op Name: SPESS OIL COMPANY
Address: 200 S. BROADWAY
CLEVELAND, OK 74020

Conductor Pipe Size: 13.375 feet: 122 WITH 160 SX CMT
Production Casing Size: 5.5 feet: 5203 WITH 125 SX CMT
Surface Casing Size: 8.625 feet: 652 WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2003 3:30 PM
Plug Co. License No.: 30288 Plug Co. Name: SPESS OIL COMPANY
Proposal Rcvd. from: TROY STACEY Company: SPESS OIL COMPANY Phone: (918) 358-5831

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 260' WITH 30 SX CMT. PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/30/2003 4:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 5181'. PERFS AT 5068-74, 5076-86, 5092-5112, 5126-46, 5154-72'. CIBP @ 5151'. DUG OUT 13 3/8" X 8 5/8" ANNULUS. FOUND CMT AT SURFACE. PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 35 SX CMT. RUN 2 3/8" TUBING IN TO SPOT PLUGS. LOADED HOLE WITH DRILLING MUD. 1ST PLUG AT 995' WITH 50 SX CMT. 2ND PLUG AT 685' WITH 50 SX CMT. 3RD PLUG AT 269' WITH 30 SX CMT. 4TH PLUG AT 30' WITH 10 SX CMT.

RECEIVED
JUL 16 2003
KCC WICHITA

Remarks: USED CLASS A CMT BY SPESS OIL. RECOVERED 2006' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 7-16-03

INV. NO. 2004060065

[Signature]
FORM 2P-2/1