

1050487

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-01,003-00-01

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Operator: Frontier Oil Co.
Name & Address 1720 Kansas State Bank Building
Wichita, KS 67202

2970 feet from S section line
2970 feet from E section line

Lease Name Einsel "A" Well # 1County Comanche 161.20Well Total Depth 4960 feetConductor Pipe: Size feetSurface Casing: Size 10 3/4" feet 277Abandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereinafter indicated Plugging Contractor Red Tiger Drilling Company License Number 5302Address 1720 Kansas State Bank Building, Wichita, KS 67202Company to plug at: Hour: 1:00 am Day: 31 Month: March Year: 1985Plugging proposal received from Ross Crawford(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 870' with 50 sx cement

2nd plug at 420' with 80 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 2:45 am Day: 31 Month: March Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement, 2nd plug at 420'
with 80 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to
surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

4-4-85
APR 04 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-9-85INV. NO. 7531

3-31

Signed Richard W. Lacey
(TECHNICIAN)