

To: 1051866 11-18
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,107-0000
C NE SW, SEC. 3, T 31 S, R 18 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Griffith B Well # 1
County Comanche 166.73
Well Total Depth 5130 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 541

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 18 Month: 11 Year: 1994

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

Perfs: 4 1/2" at 5128' w/160 sx cement, PBD 5020'; Perfs at 4953-76, 4986-90, 5002-06'
1st plug set CIBP over perfs at 4900',
2nd plug at 1300' with 50 sx cement,
3rd plug at 570' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5 p.m. Day: 18 Month: 11 Year: 1994

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4900' and dumped 2 sx cement on top,
Pumped through 4 1/2" casing:
2nd plug at 1300' with 50 sx cement,
3rd plug at 570' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3562' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

VOID
I hereby certify that I have observed this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 11-29-94
INV. NO. 41738
11-18

RECEIVED
NOV 29 1994
11-22-94
DIVISION COM.
SAC