

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21155-00-00
Spot: W2SESW Sec/Twnshp/Rge: 29-31S-19W
660 feet from S Section Line, 1850 feet from W Section Line
Lease/Unit Name: ELLIS TRUST Well Number: 29-1
County: COMANCHE Total Vertical Depth: 6013 feet

Operator License No.: 32384
Op Name: COMANCHE RESOURCES COMPANY
Address: 9520 N. MAY AVENUE STE 370
OKLAHOMA CITY, OK 73120

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 656 WITH 250 SX CMT
Production: Size 4.5 feet: 6014 WITH 285 SX CMT
Liner: Size _____ feet: _____ 95.42

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/10/2001 11:45 AM

Plug Co. License No.: 31705 Plug Co. Name: H & K PLUGGING AND SALVAGE

Proposal Rcvd. from: JIM CONNER Company: H & K PLUGGING AND SALVAGE Phone: (806) 665-2550

Proposed Plugging Method: SET CIBP @ 5100' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1050' WITH 50 SX CMT. 2N DPLUG AT 670' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 05/10/2001 1:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 6013'. PERFS AT 5189-91, 5206-10'. SET CIBP @ 5100' WITH 2 1/2 SX CMT ON TOP WITH BAILER. LOAD HOLE WITH GEL. 1ST PLUG RUN 2 3/8" TUBING TO 1050' AND SPOT 50 SX CMT. 2ND PLUG PULL TUBING TO 670' AND SPOT 50 SX CMT. 3RD PLUG PULL TO 40' AND SPOT 15 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

INVOICED
DATE 5-16-01
TRF. NO. 2001061819
RECEIVED
KANSAS CORPORATION COMMISSION
MAY 16 2001
05-16-2001
CONSERVATION DIVISION

Remarks: USED CLASS A COMMON CEMENT BY H & K PLUGGING. RECOVERED 3537' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

Signed _____
(TECHNICIAN)

MAY 14 2001

Form 273