

3-9

To: 1 031064
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15-033-20,167-00-00C NE SE, SEC. 36, T 31 S, R 19 W/E1980 feet from S section line660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152Lease Name Burt Well # 1Operator: Lee Banks OilCounty Comanche 16.8.12Name & Address 200 West Douglas, Suite 550Well Total Depth 5173 feetWichita, KS 67202Conductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 388Abandoned Oil Well Gas Well X Input Well SWD Well D&A Other well as hereinafter indicated Plugging Contractor Rockhold Engineering License Number 5111Address Box 698, Great Bend, KS 67530Company to plug at: Hour: 10:45 a.m. Day: 9 Month: 3 Year: 19 90Plugging proposal received from Jim Rockhold(company name) Rockhold Engineering (phone) 316-792-2506were: 4 1/2" at 5173' PBTB 4350' Perfs at 4972-4294' Plug set at 4790' & 4350'1st plug sand back to 4240' and dump 4 sx cement on top of sand through bailer,2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"wiper plug and pump 100 sx cement.Plugging Proposal Received by Mike Wilson
(TECHNICIAN)Plugging Operations attended by Agent?: All X Part None Operations Completed: Hour: 11:30 a.m. Day: 9 Month: 3 Year: 19 90ACTUAL PLUGGING REPORT 1st plug sanded back to 4240' and dumped 4 sx cement on top of sand through bailer,2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 350 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3170' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)INVOICED 0310 / 0000000 observe this plugging.DATE 3-14-90Signed Steve Hume
(TECHNICIAN)INV. NO. 27632

3-9