

1 030615

033

API NUMBER 15- ~~023~~-20,682-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW SE, SEC. 1, T 31 S, R 19 W/A
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Robbins Well # 1

Operator: Hummon Corporation
Name & Address: 400 One Main Place
Wichita, KS 67202

County Comanche
Well Total Depth 5210 169.33 feet
Conductor Pipe: Size feet
Surface Casing: Size 13 3/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 8:30 am Day: 14 Month: December Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 5209' PBD 5189' Perfs at 5153-5157'; 5109-5114'; 4964-4968'

1st plug sand back to 4915' and dump 5 sx cement on top of sand through bailer.

Pump through 5 1/2" casing with mud between plugs

Circulate mud from 1600' (68 sx)

2nd plug at 1020' with 50 sx cement 3rd plug at 300' with 60 sx cement

solid bridge - hulls - plug at 40' -- cement to surface with

4th plug 25 sx cement Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15 pm Day: 14 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4915' and dumped 5 sx cement on top of sand through bailer, circulated mud from 1600' with 68 sx mud. 2nd plug at 1020' with 50 sx cement, 3rd plug at 300' with 60 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 25 sx cement.

Remarks: Recovered 2900' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 20 1985

INV. NO. 11677

DEC 20 1985
12-20-1985
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Durrant
(TECHNICIAN)