

9-14

To: 1 040162
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,731-0000

C SE SW, SEC. 7, T 31 S, R 18 W/EX

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Sherman Well # 1

Operator: Hummon Corporation

County Comanche 171.28

Name & Address 400 One Main Place

Well Total Depth 5270 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 769

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 14 Month: 9 Year: 19 88

Plugging proposal received from Dick Davis

(company name) H-30 Drilling, Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2105'

1st plug at 1000' with 40 sx cement,

2nd plug at 790' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
9-16-88
CONSERVATION DIVISION
Wichita, Kansas
Michael Lacey
(TECHNICIAN)

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 a.m. Day: 14 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1000' with 40 sx cement,

2nd plug at 790' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

Water well plugged with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(if additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

DATE 9-22-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 22366

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: September 2 1988
month day year

API Number 15-033-20,731-0000

OPERATOR: License # 5050
 Name Hummon Corporation
 Address 400 One Main Place
 City/State/Zip Wichita, KS 67202
 Contact Person Kenneth S. White
 Phone (316) 263-8521

C. SE. SW. Sec. 7 Twp. 31 S, Rg. 18 East West
660 Ft. from South Line of Section
3300 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107
 Name H-30 Drilling, Inc.
 City/State Wichita, Kansas

Nearest lease or unit boundary line 660 feet
 County Comanche
 Lease Name Sherman Well # 1

Well Drilled For: Well Class: Type Equipment:
 Oil Storage Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Ground surface elevation _____ feet MSL
 Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no

IF OWWO: old well info as follows:

Depth to bottom of fresh water 250
 Depth to bottom of usable water 280 350

Operator _____
 Well Name _____
 Comp Date _____ Old Total Depth _____

Surface pipe by Alternate: 1 X 2
 Surface pipe planned to be set 450'
 Conductor pipe required none
 Projected Total Depth 5200 feet
 Formation Mississippi

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 8/27/89 Signature of Operator or Agent Kenneth S. White Title Vice President

For KCC Use:

Conductor Pipe Required _____ feet; Minimum Surface Pipe Required 370' feet per Alt. (1) X

This Authorization Expires 2-29-89 Approved By LKM 8-29-89

EFFECTIVE DATE: 8-29-88

Spud 9-2-88 12:00
750' 8 1/8

(WW)

C. SE. SW. Sec. 7 Twp. 31 S, Rg. 18 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1080'
 1st plug @ ft. deep. Base Anhydrite or formation with 50 sacks feet of 60/40 Poz. Mix, .6% gel
 2nd plug @ ft. deep. 520' or formation with 60 sacks feet of 60/40 Poz. Mix, .6% gel
 3rd plug @ ft. deep. 0-40 or formation with 10 sacks feet of 60/40 Poz. Mix, .6% gel
 4th plug @ ft. deep _____ or formation with _____ feet of _____
 5th plug @ ft. deep _____ or formation with _____ feet of _____

(2) Rathole to surface minus 5 feet 15 sacks (b) Mousehole to surface minus 5 feet 10 sacks

PUSHER Pick Davis w/H-30
 TD 5270 FORMATION MISS
 SURFACE PIPE 8 9/8 @ 769
 ANHYDRITE 2106 ELEVATION
 STARTING TIME & DATE 9-14-88 3:00 AM
 COMPLETION TIME & DATE 9-14-88 5:30 AM
 1st PLUG @ 1000 FT. W/ 40 SX
 2nd PLUG @ 790 FT. W/ 50 SX
 3rd PLUG @ 40 FT. W/ 10 SX
 4th PLUG @ _____ FT. W/ _____ SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ _____ SX
 WATER WELL PLUGGED W/ 15 SX
 CEMENT COMPANY SBG
 TECHNICIAN Lacey

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 16 1988
 9-16-88
 CONSERVATION DIVISION
 Wichita, Kansas

60/40 6%